BRUHAT BANGALORE MAHANAGARA PALIKE

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/22/2017-18, Date:16.02.2018

Package-4, includes 4 works of Rs.195.00 lakhs

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of ABHIJIT A ( )	
				In Figures	In Words
1	2376.65	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. Pg No.141.Item No.19.1)	Cum	86.0	Rupees Eighty Six Only
2	857.02	KSRRB 300-1. Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.. Pg No.141.Item No.19.1)	Cum	166.0	Rupees One Hundred Sixty Six Only
3	498.96	Removing & Refixing Stone slabs of drains and Pointing in C.M(1:3) (P.No.25, I.No.5.33 of PW, P&IWTD SR 2016-17)	Sqm	80.0	Rupees Eighty Only
4	295.44	Providing granite slabs of selected quality roughly dressed and fixed in cementer mortar (1:6) including fixing curing etc., complete. Pg No.25, Item No.5.31.1 (7.5 cms thick)	Sqm	660.0	Rupees Six Hundred Sixty Only
5	1015.2	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, conrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification . (Pg.No.12, It.4.3)	Cum	5000.0	Rupees Five Thousand Only
6	16.38	KSRB 4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.53cum, machine mixed concrete laid in layers not exceeding 15cms thick well compacted in foundation plinth and cills including cost of all materials, labour HOM of machinery curing complete as per specifications.(Item No.4.6, Page No.12)	Cum	5750.0	Rupees Five Thousand Seven Hundred Fifty Only
7	31.59	KSRB 5.3-1:Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms hign, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications.(P-23. Item No. 5.6)	Cum	4400.0	Rupees Four Thousand Four Hundred Only
8	28.35	b) With avaialable stones	Cum	4250.0	Rupees Four Thousand Two Hundred Fifty Only
9	238.2	KSRB 5.3-1:Providing ruled pointing of course stone msonry with cement mortar 1:3 20 mm deep, after raking joints to depth of 20 mm nicley lining, including cost of materials, labour, curing etc., complete as per specifications and directions of the engineer-in-charge. (P-112, Item No. 15.8)	Sqm	35.0	Rupees Thirty Five Only

31/10
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92
31/10

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of ABHIJIT A ( )	
				In Figures	In Words
10	731.75	Cement concrete pavement. Construction of un-reinfirced plain cement concrete pavement, thickness as per deisgn, over a prepraed sub base with OPC cement or any other type as per clause 1051..2.2 with 25mm and down size graded granite metal coarse aggregates and fine aggregates ,with superplastiser @ 3lts confirming to IS9103-1999 REAFFIRMED-2008, Mixed in a concrete mixer of not less than 0.6 cum capacity and approximate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates inlcuding levelling the form work as per drawing) and spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continous operation including, provision of contraction, expansion, construction operation including longitudinal joints, including groove cutting charges joint filler, sparation menebrane, sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specfication.M20 (AT 300 Kg per cum coarse aggregats @ 0.69cum and fine aggregate @0.43cum) (Pg No.177, It No.22.6.2)	Cum	5400.0	Rupees Five Thousand Four Hundred Only
11	4898.5	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cst of generator, HOM of machinery screed vibaratory, power floater, blade and disc etc., with all leads and lift. (P177, It No. 22.7)	Sqm	95.0	Rupees Ninety Five Only
12	237	KSSRB M 400-17: Providing laying, spreading and compacting graded fine aggregate to wet mix macadam specificationns including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surfce and compating with vibratory roller to achieve the desired density complete as per specifications. MORTH specifications no. 406(P-157., It No: 20.18)	Cum	1750.0	Rupees One Thousand Seven Hundred Fifty Only
13	1185	KSRRB 500-07: Providing and applying primer coat with SS bitumen emulsion on prepared surface o fgranular sub base such as WMM including cleaning of road surface and spraying primer at the rate of 0.6kg/m using mechanical means complete as per specifications., Pg No. 161. Item No. 21.6)	Sqm	27.0	Rupees Twenty Seven Only
14	47.4	Providing and laying bituminous concrete40MM thick with hotmix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filleeer, transporting of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with paver finisher to the required gradde, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to acheive the desired compaction as per MORTH specifications clause No.509 complete in all respects complete as per specifications. using 40/60 TPH capacity H.M.P with mechanical paver Gr-11(30mm to 45mm) with 5.4% of modified binder consisting of 4.97% VG-10 bitumen (80/100) grade and 0.43% of plastomeric thermoplastics(Waste plastic)(Page No.172, It No.21.78.6)	Cum	7100.0	Rupees Seven Thousand One Hundred Only
15	80.1	KSRB 4.2.2: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastizers @ 3lts confirming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts butresses string or lacing courses parapets copings, bed blocks , plain windows cills fillets etc., including cost of all materials labour HOM of machinery curing complete as per specifications. Seocifications No. KBS 4.1,4.6 (Page NO. 13, Item NO. 4.11)	cum	6300.0	Rupees Six Thousand Three Hundred Only
16	48.06	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.(Page No.17, Item No.17)	tonne	64000.0	Rupees Sixty Four Thousand Only

31/10

Executive Engineer
Byatarayanapura Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of ABHIJIT A ( )	
				In Figures	In Words
17	640.8	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge.(Page No.16, Item NO.4.32)	Sqm	380.0	Rupees Three Hundred Eighty Only
18	3160.77	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH Chapter 1 (Page 118, item No. 17.1)	Sqm	95.5	Rupees Ninety Five and Fifty Paise Only

Signature of the Contractor

31/10

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

Executive Engineer
Byarayanapura Division
BBMP, Bangalore-92

31/10